


DATE SUBMITTED 01/30/2018
 SUBMITTED BY COMMUNITY DEVELOPMENT DIRECTOR
 DATE ACTION REQUIRED 02/07/2018

COUNCIL ACTION (x)
 PUBLIC HEARING REQUIRED ()
 RESOLUTION ()
 ORDINANCE 1ST READING ()
 ORDINANCE 2ND READING ()
 CITY CLERK'S INITIALS 

**IMPERIAL CITY COUNCIL
 AGENDA ITEM**

SUBJECT: DISCUSSION/ACTION:
DOGWOOD ROAD PAVEMENT REHABILITATION FROM ATEN BOULEVARD TO SOUTHEAST CITY LIMIT
 FEDERAL AID PROJECT # RSTP-5134(019) - CITY OF IMPERIAL BID NO. 2017-03
 1. APPROVAL OF BALANCING CHANGE ORDER
 2. ACCEPTANCE OF COMPLETED WORK

DEPARTMENT INVOLVED: PLANNING DIVISION

BACKGROUND/SUMMARY:
 The City was able to obtain funding through the Regional Surface Transportation Program (RSTP) for the rehabilitation and reconstruction of the above-referenced section of Dogwood Rd.
 The work included grinding existing AC pavement, HMA leveling course, install ARAM, ARHM overlay, new pavement striping, installation of a traffic loop and road traffic control around the construction zones.
 An individual contract was awarded to Aggregate Products, Inc. through competitive bidding process for the proper completion of the above-described work.
 All work was completed per Approved Improvement Plans. Final quantities have been accounted in the balancing change order attached herewith for review and approval.
 The construction project was successfully completed on December 30, 2017.

FISCAL IMPACT:
 Original Contract Sum: \$ 289,913.50
 Net Change by C.O. : \$ 15,255.30 (+5.26%)
 Total Amount Including C.O.: \$ **305,168.80**

ADMIN SERVICES SIGN INITIALS *Finance* 

STAFF RECOMMENDATION: Staff recommends City Council approval of balancing change order and acceptance closing of the project.

DEPT. INITIALS OM

MANAGER'S RECOMMENDATION:

CITY MANAGER'S INITIALS *Office* 

MOTION:
 SECONDED: APPROVED () REJECTED ()
 AYES: DISAPPROVED () DEFERRED ()
 NAYES:
 ABSENT: REFERRED TO:

CITY OF IMPERIAL

EXHIBIT "A": Balancing Change Order Report

FOR

Dogwood Road Pavement Rehabilitation from Aten Boulevard to Southeast City Limit
 FEDERAL AID PROJECT # RSTP-5134(019) / MPO ID: IMP 160406 - BID NO. 2017-03

Item No.	Bid Item Description	Units	Estimated Quantity	Unit Price (\$)	Contract Amount (\$)	As-Built Quantity	As-Built Amount (\$)	Difference
1.	Mobilization (a)	LS	1	30,000.00	30,000.00	1	30,000.00	0
2.	Traffic Control & Construction Area Signs	LS	1	11,900.00	11,900.00	1	11,900.00	0
3.	Cold Plane AC – Joint Detail per Detail B on Sheet C1	SF	1,500	4.75	7,125.00	1,500	7,125.00	0
4.	3/4" Leveling Course: 1/2" Hot Mix Asphalt Type A and SS1h Tack Coat	TON	320	139.00	44,480.00	378.49	52,610.11	8,130.11
5.	3/8" Asphalt Rubber Aggregate Membrane (ARAM)	SF	70,700	0.98	69,286.00	69,147.00	67,764.06	-1,521.94
6.	1.5" Asphalt Rubber Hot Mix (ARHM) Overlay: 1/2" Aggregate / Type Gap Graded (GG)	TON	640	139.00	88,960.00	726.67	101,007.13	12,047.13
7.	Shoulder Backing at Edge of Pavement using Class II Base per Detail C on Sheet C1	LF	5,050	4.25	21,462.50	5,050	21,462.50	0
8.	Pavement Striping & Raised Pavement Markers	LS	1	6,100.00	6,100.00	1	6,100.00	0
9.	Install Traffic Loop	EA	1	6,000.00	6,000.00	1	6,000.00	0
10.	SWPPP Permit / SWPPP Implementation	LS	1	1,200.00	1,200.00	1	1,200.00	0
11.	Install a Dig Out (4 inch thick ARHM)	SF	400	8.50	3,400.00	0	-	-3,400
TOTAL =					\$ 289,913.50		\$ 305,168.80	\$15,255.30



GENERAL ENGINEERING LIC. NO. 698013

VIA FAX: (760) 355-4718
ORIGINAL BY MAIL

January 25, 2018

Jesus Villegas
City of Imperial
420 South Imperial Ave.
Imperial, CA 92251

RE: Dogwood Road Pavement Rehabilitation
RSTP-5134(019)
API Job No. 0074

Dear Mr. Villegas:

This is to notify you that all work on referenced project have been completed as of December 30, 2017.

Very truly yours,


John Velez

JV/jt

9500 Beverly Road
Pico Rivera CA 90660-2135

E-mail: enrgmainc@earthlink.net

Tel: (323) 558-8000
Fax: (323) 558-8055