

EXHIBIT 1
PHOTO REPORT – WATER LEAKAGE: “F” & 11TH STREETS INTERSECTION.



EXHIBIT 1
PHOTO REPORT – WATER LEAKAGE: “F” & 11TH STREETS INTERSECTION.



EXHIBIT 1
PHOTO REPORT – WATER LEAKAGE: “F” & 11TH STREETS INTERSECTION.



EXHIBIT 1
PHOTO REPORT – WATER LEAKAGE: “F” & 11TH STREETS INTERSECTION.



EXHIBIT 2



DIR: 1000000085
CA License 89

CCO Proposal - Asphalt Repairs 11th and "F" ST

Granite Construction Company
38000 Monroe Street
Indio, CA 92203
Francisco.duffy@gcinc.com
760-399-6101

April 20, 2020
Rev 2

PROJECT COI Storm Drain Project
Site: 11th St, Imperial CA

PREPARED FOR Jesus Villegas
City of Imperial
jvillegas@cityofimperial.org
760-604-3251

ITEM	DESCRIPTION	QUAN	UNIT	UNIT PRICE	EXT PRICE
1	PAVEMENT REPAIR SAW CUT	144	LF	\$17	\$2,448
2	REMOVE AC PAVEMENT	36	CY	\$228	\$8,208
3	GRADING	2280	SF	\$6	\$13,680
4	LAY MIX DIGOUTS ENDS	55	TN	\$383	\$21,065
5	PAVEMENT MARKINGS	1	EA	\$3,500	\$3,500
				TOTAL:	\$48,901

Scope

- Saw cut, remove and dispose of existing asphalt
- Remove and dispose of 9" of saturated subgrade replace with Geogrid and 9" of class II base.
- Pave 4" of 1/2" HMA PG70-10
- Complete Pavement Markings; legend and lines shall be thermoplastic as illustrated on approved improvement plans.

Clarifications

- Subgrade to be compacted to 90% of Maximum Density, class II base material to be compacted to 95% maximum density per ASTM D1557.
- Supply compaction reports of subgrade, newly placed class II base material, as well as HMA.